

**FRESNO COUNTY FIRE PROTECTION DISTRICT**

**ADDENDUM NO. 1**

**DATE:** February 10<sup>th</sup>, 2025

**RFQ:** FIRE STATION 82 & MAINTENANCE SHOP ASPHALT & CONCRETE

**DUE DATE:** TUESDAY FEBRUARY 18<sup>TH</sup>, 2025 BY 4:00 P.M. PST

**TO:** ALL RFQ DOCUMENT HOLDERS

This addendum clarifies the original scope of work as noted below. This addendum consists of one page

**Scope of Work**

Fresno County Fire Protection District is soliciting quotes for the provision for all equipment, materials, and labor necessary for a durable and high-performance concrete and asphalt replacement that will withstand heavy loads high foot and vehicle traffic. Approximate square footage for the Concrete Pad is 6,080 Sq Ft. we are also exploring our options for concrete work **[Fiber Reinforcement Vs Rebar]**. Asphalt Replacement is approximately 35,750 Sq Ft. This project includes two construction areas.

Please provide us with your best quote for the following services:

**Slab to meet or exceed the following requirements**

- 1. Fiber reinforcement with expansion joints cut every 10' each way, 8" thick 4000 PSI
- 2. Rebar #3 @ 18 expansion joints every 12' to 15' each way, 6" thick 4000 PSI
- 3. Concrete apron 50' long
- 4. Smooth finish

**Asphalt to meet or exceed the following requirements**

- 1. 4" asphalt over 8" base rock section
- 2. ¾" aggregate for both lifts on the asphalt

**Edit, Page 1, Scope of Work-Exhibit B**

11 Parking Stalls for Striping  
Ground drain rework

**Edit, Page 2 Submission Due Date**

New proposal due date February 18<sup>th</sup>, 2025, by 4:00 PM PST via email